G1

VOLTAGE: 277/480 | PH & WIRES: 3P 4W | BUSES: 200
MAIN BREAKER: MLO | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: GARAGE | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
PANEL GP1 VIA XFMR	50	3	1	1	31992	14492	---	---	2161	2	2	3	15	MAU-1
	-	-	-	3		---	10142	---		4	-	-	-	
	-	-	-	5		---	---	9518		6	-	-	-	
EDC-1	70	1	7	7	15000	17106	---	---	6318	8	8	3	15	MAU-2
EMER & BATT LTG - GARAGE	15	1	9	9	148	---	2254	---		10	-	-	-	
SPARE	20	1	11	11	0	---	---	2106		12	-	-	-	
PREPARED SPACE		1	13	13	0	499	---	---	1496	14	14	3	15	EF-1
PREPARED SPACE		1	15	15	0	---	499	---		16	-	-	-	
PREPARED SPACE		1	17	17	0	---	---	499		18	-	-	-	
PREPARED SPACE		1	19	19	0	720	---	---	2161	20	20	3	15	VEF-1
PREPARED SPACE		1	21	21	0	---	720	---		22	-	-	-	
PREPARED SPACE		1	23	23	0	---	---	720		24	-	-	-	
PREPARED SPACE		1	25	25	0	0	---	---	0	26	26	1		PREPARED SPACE
PREPARED SPACE		1	27	27	0	---	0	---	0	28	28	1		PREPARED SPACE
PREPARED SPACE		1	29	29	0	---	---	0	0	30	30	1		PREPARED SPACE
PREPARED SPACE		1	31	31	0	0	---	---	0	32	32	1		PREPARED SPACE
PREPARED SPACE		1	33	33	0	---	0	---	0	34	34	1		PREPARED SPACE
PREPARED SPACE		1	35	35	0	---	---	0	0	36	36	1		PREPARED SPACE
PREPARED SPACE		1	37	37	0	0	---	---	0	38	38	1		PREPARED SPACE
PREPARED SPACE		1	39	39	0	---	0	---	0	40	40	1		PREPARED SPACE
PREPARED SPACE		1	41	41	0	---	---	0	0	42	42	1		PREPARED SPACE
TOTAL AMPS: 71.3						32817	13615	12843	TOTAL WATTS: 59275					

REMARKS:
FED FROM PANEL MDP.

01/13/2015

G2

VOLTAGE: 277/480 | PH & WIRES: 3P 4W | BUSES: 200
MAIN BREAKER: MLO | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: GARAGE | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
PANEL GP2 VIA XFMR	50	3	1	1	55088	20121	---	---	1496	2	2	3	15	EF-2
	-	-	-	3		---	19893	---		4	-	-	-	
	-	-	-	5		---	---	16571		6	-	-	-	
SPARE	20	1	7	7	0	720	---	---	2161	8	8	3	15	VEF-2
SPARE	20	1	9	9	0	---	720	---		10	-	-	-	
SPARE	20	1	11	11	0	---	---	720		12	-	-	-	
PREPARED SPACE		1	13	13	0	0	---	---	0	14	14	1		PREPARED SPACE
PREPARED SPACE		1	15	15	0	---	0	---	0	16	16	1		PREPARED SPACE
PREPARED SPACE		1	17	17	0	---	---	0	0	18	18	1		PREPARED SPACE
PREPARED SPACE		1	19	19	0	0	---	---	0	20	20	1		PREPARED SPACE
PREPARED SPACE		1	21	21	0	---	0	---	0	22	22	1		PREPARED SPACE
PREPARED SPACE		1	23	23	0	---	---	0	0	24	24	1		PREPARED SPACE
PREPARED SPACE		1	25	25	0	0	---	---	0	26	26	1		PREPARED SPACE
PREPARED SPACE		1	27	27	0	---	0	---	0	28	28	1		PREPARED SPACE
PREPARED SPACE		1	29	29	0	---	---	0	0	30	30	1		PREPARED SPACE
PREPARED SPACE		1	31	31	0	0	---	---	0	32	32	1		PREPARED SPACE
PREPARED SPACE		1	33	33	0	---	0	---	0	34	34	1		PREPARED SPACE
PREPARED SPACE		1	35	35	0	---	---	0	0	36	36	1		PREPARED SPACE
PREPARED SPACE		1	37	37	0	0	---	---	0	38	38	1		PREPARED SPACE
PREPARED SPACE		1	39	39	0	---	0	---	0	40	40	1		PREPARED SPACE
PREPARED SPACE		1	41	41	0	---	---	0	0	42	42	1		PREPARED SPACE
TOTAL AMPS: 70.7						20841	20613	17291	TOTAL WATTS: 58745					

REMARKS:
FED FROM PANEL MDP.

01/13/2015

G3

VOLTAGE: 277/480 | PH & WIRES: 3P 4W | BUSES: 400
MAIN BREAKER: MLO | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: WASH BAY | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
TRUCK WASH (GANTRY)	30	3	1	1	12465	4875	---	---	2161	2	2	3	15	MAU-3
	-	-	-	3		---	4875	---		4	-	-	-	
	-	-	-	5		---	---	4875		6	-	-	-	
TRUCK WASH (PUMP SKID)	100	3	7	7	63987	62048	---	---	122157	8	8	3	200	TRUCK WASH (STRIPPER)
	-	-	-	9		---	62048	---		10	-	-	-	
	-	-	-	11		---	---	62048		12	-	-	-	
TRUCK WASH (PRESS WASH)	30	3	13	13	9141	3047	---	---	0	14	14	1	20	SPARE
	-	-	-	15		---	3047	---	0	16	16	1	20	SPARE
	-	-	-	17		---	---	3047	0	18	18	1	20	SPARE
PREPARED SPACE		1	19	19	0	0	---	---	0	20	20	1		PREPARED SPACE
PREPARED SPACE		1	21	21	0	---	0	---	0	22	22	1		PREPARED SPACE
PREPARED SPACE		1	23	23	0	---	---	0	0	24	24	1		PREPARED SPACE
PREPARED SPACE		1	25	25	0	0	---	---	0	26	26	1		PREPARED SPACE
PREPARED SPACE		1	27	27	0	---	0	---	0	28	28	1		PREPARED SPACE
PREPARED SPACE		1	29	29	0	---	---	0	0	30	30	1		PREPARED SPACE
PREPARED SPACE		1	31	31	0	0	---	---	0	32	32	1		PREPARED SPACE
PREPARED SPACE		1	33	33	0	---	0	---	0	34	34	1		PREPARED SPACE
PREPARED SPACE		1	35	35	0	---	---	0	0	36	36	1		PREPARED SPACE
PREPARED SPACE		1	37	37	0	0	---	---	0	38	38	1		PREPARED SPACE
PREPARED SPACE		1	39	39	0	---	0	---	0	40	40	1		PREPARED SPACE
PREPARED SPACE		1	41	41	0	---	---	0	0	42	42	1		PREPARED SPACE
TOTAL AMPS: 252.6						69970	69970	69970	TOTAL WATTS: 209910					

REMARKS:
FED FROM PANEL MDP.

01/13/2015

PANELBOARD G3 SHALL BE NEMA 4X RATED UNLESS LOCATED WITHIN A WATER TIGHT ENCLOSURE/ROOM.

GP1

VOLTAGE: 120/208 | PH & WIRES: 3P 4W | BUSES: 100
MAIN BREAKER: 100A MAIN BRKR | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: GARAGE | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
OH DOOR - GARAGE	20	1	1	1	1176	4926	---	---	7500	2	2	2	50	WELDER RCPT - GARAGE
OH DOOR - GARAGE	20	1	3	3	1176	---	4926	---		4	-	-	-	
OH DOOR - GARAGE	20	1	5	5	1176	---	---	4926	7500	6	6	2	50	WELDER RCPT - GARAGE
OH DOOR - GARAGE	20	1	7	7	1176	4926	---	---		8	-	-	-	
OH DOOR - GARAGE	20	1	9	9	1176	---	1376	---	200	10	10	1	20	RCPTS - COLUMN MTD
OH DOOR - GARAGE	20	1	11	11	1176	---	---	1376	200	12	12	1	20	RCPTS - COLUMN MTD
SPARE	20	1	13	13	0	200	---	---	200	14	14	1	20	* RCPTS - AT STRUCTURE
SPARE	20	1	15	15	0	---	200	---	200	16	16	1	20	* RCPTS - AT STRUCTURE
SPARE	20	1	17	17	0	---	---	200	200	18	18	1	20	* RCPTS - AT STRUCTURE
SPARE	20	1	19	19	0	200	---	---	200	20	20	1	20	* RCPTS - AT STRUCTURE
SPARE	20	1	21	21	0	---	600	---	600	22	22	1	20	RCPTS - GARAGE
SPARE	20	1	23	23	0	---	---	600	600	24	24	1	20	RCPTS - GARAGE
SPARE	20	1	25	25	0	800	---	---	800	26	26	1	20	RCPTS - GARAGE
SPARE	20	1	27	27	0	---	400	---	400	28	28	1	20	RCPTS - GARAGE
SPARE	20	1	29	29	0	---	---	800	800	30	30	1	20	RCPTS - GARAGE
SPARE	20	1	31	31	0	800	---	---	800	32	32	1	20	RCPTS - GARAGE
SPARE	20	1	33	33	0	---	0	---	0	34	34	1	20	SPARE
RCPTS - ROOF MTD	20	1	35	35	200	---	---	200	0	36	36	1	20	SPARE
UH-1	30	1	37	37	1920	1920	---	---	0	38	38	1	20	SPARE
UH-2	30	1	39	39	1920	---	1920	---	0	40	40	1	20	SPARE
EF-3	15	1	41	41	696	---	---	696	0	42	42	1	20	SPARE
TOTAL AMPS: 88.9						13772	9422	8798	TOTAL WATTS: 31992					

REMARKS:
FED FROM PANEL G1 VIA TRANSFORMER.

01/13/2015

GP2

VOLTAGE: 120/208 | PH & WIRES: 3P 4W | BUSES: 100
MAIN BREAKER: 100A MAIN BRKR | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: GARAGE | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
RCPTS - EXT POLE MOUNTED	20	1	1	1	1900	5650	---	---	7500	2	2	2	50	WELDER RCPT - GARAGE
RCPTS - EXT POLE MOUNTED	20	1	3	3	1900	---	5650	---		4	-	-	-	
RCPTS - EXT POLE MOUNTED	20	1	5	5	1900	---	---	5650	7500	6	6	2	50	WELDER RCPT - GARAGE
OH DOOR - GARAGE	20	1	7	7	1176	4926	---	---		8	-	-	-	
OH DOOR - GARAGE	20	1	9	9	1176	---	4926	---	7500	10	10	2	50	WELDER RCPT - GARAGE
OH DOOR - GARAGE	20	1	11	11	1176	---	---	4926		12	-	-	-	
OH DOOR - GARAGE	20	1	13	13	1176	4926	---	---	7500	14	14	2	50	WELDER RCPT - GARAGE
RCPTS - DEF PUMP	20	1	15	15	700	---	4450	---		16	-	-	-	
SPARE	20	1	17	17	0	---	---	200	200	18	18	1	20	RCPTS - COLUMN MTD
SPARE	20	1	19	19	0	200	---	---	200	20	20	1	20	RCPTS - COLUMN MTD
SPARE	20	1	21	21	0	---	200	---	200	22	22	1	20	* RCPTS - AT STRUCTURE
SPARE	20	1	23	23	0	---	---	200	200	24	24	1	20	* RCPTS - AT STRUCTURE
SPARE	20	1	25	25	0	200	---	---	200	26	26	1	20	* RCPTS - AT STRUCTURE
RCPTS - ROOF MTD	20	1	27	27	400	---	600	---	200	28	28	1	20	* RCPTS - AT STRUCTURE
UH-3	30	1	29	29	1920	---	---	2520	600	30	30	1	20	RCPTS - GARAGE
UH-4	30	1	31	31	1920	2520	---	---	600	32	32	1	20	RCPTS - GARAGE
EF-4 & 5	20	1	33	33	1392	---	1992	---	600	34	34	1	20	RCPTS - GARAGE
RCPTS - WASH BAY	20	1	35	35	400	---	---	1000	600	36	36	1	20	RCPTS - GARAGE
RCPTS - WASH BAY	20	1	37	37	400	1200	---	---	800	38	38	1	20	RCPTS - GARAGE
OH DOOR - GARAGE	20	1	39	39	1176	---	1576	---	400	40	40	1	20	RCPTS - TOOL CRIB
OH DOOR - GARAGE	20	1	41	41	1176	---	---	1576	400	42	42	1	20	RCPTS - TOOL CRIB
TOTAL AMPS: 153						19622	19394	16072	TOTAL WATTS: 55088					

REMARKS:
FED FROM PANEL G2 VIA TRANSFORMER., * = GFCI CIRCUIT BREAKER

01/13/2015

L1

VOLTAGE: 277/480 | PH & WIRES: 3P 4W | BUSES: 200
MAIN BREAKER: MAIN BUS & LUGS | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: MAIN ELECTRICAL ROOM | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
LTG - GARAGE	20	1	1	1	4242	5684	---	---	1442	2	2	1	20	LTG - EXT BLDG MTD
LTG - GARAGE	20	1	3	3	3420	---	5763	---	2343	4	4	1	20	LTG - EXT POLES (FRONT)
SPARE	20	1	5	5	0	---	---	1704	1704	6	6	1	20	LTG - EXT POLES (BACK)
LTG - STORAGE/MEZZ/BREAK	20	1	7	7	3579	5922	---	---	2343	8	8	1	20	LTG - EXT POLES (BACK)
LTG - OFFICE AREA	20	1	9	9	2881	---	3381	---	500	10	10	1	20	LTG - CONT PNL (LV1)
LTG - OFFICE AREA	20	1	11	11	3261	---	---	3261	0	12	12	1	20	SPARE
LTG - WASH BAY	20	1	13	13	1760	1760	---	---	0	14	14	1	20	SPARE
LTG - SHIPPING	20	1	15	15	1266	---	1266	---	0	16	16	1	20	SPARE
SPARE	20	1	17	17	0	---	---	0	0	18	18	1	20	SPARE
PREPARED SPACE		1	19	19	0	0	---	---	0	20	20	1		PREPARED SPACE
PREPARED SPACE		1	21	21	0	---	0	---	0	22	22	1		PREPARED SPACE
PREPARED SPACE		1	23	23	0	---	---	0	0	24	24	1		PREPARED SPACE
PREPARED SPACE		1	25	25	0	0	---	---	0	26	26	1		PREPARED SPACE
PREPARED SPACE		1	27	27	0	---	0	---	0	28	28	1		PREPARED SPACE
PREPARED SPACE		1	29	29	0	---	---	0	0	30	30	1		PREPARED SPACE
PREPARED SPACE		1	31	31	0	0	---	---	0	32	32	1		PREPARED SPACE
PREPARED SPACE		1	33	33	0	---	0	---	0	34	34	1		PREPARED SPACE
PREPARED SPACE		1	35	35	0	---	---	0	0	36	36	1		PREPARED SPACE
PREPARED SPACE		1	37	37	0	0	---	---	0	38	38	1		PREPARED SPACE
PREPARED SPACE		1	39	39	0	---	0	---	0	40	40	1		PREPARED SPACE
PREPARED SPACE		1	41	41	0	---	---	0	0	42	42	1		PREPARED SPACE
TOTAL AMPS: 34.6						13366	10410	4965	TOTAL WATTS: 28741					

REMARKS:
FED FROM PANEL MDP.

01/13/2015

MDP

VOLTAGE: 277/480 | PH & WIRES: 3P 4W | BUSES: 800
MAIN BREAKER: MLO | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: GARAGE | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
PANEL L1	100	3	1	1	28741	83336	---	---	209911	2	2	3	400	PANEL G3
	-	-	-	3		---	80380	---		4	-	-	-	
	-	-	-	5		---	---	74935		6	-	-	-	
PANEL G1	200	3	7	7	59275	37000	---	---	12548	8	8	3	20	RTU-1
	-	-	-	9		---	17798	---		10	-	-	-	
	-	-	-	11		---	---	17026		12	-	-	-	
PANEL G2	200	3	13	13	58745	26963	---	---	18365	14	14	3	30	RTU-2
	-	-	-	15		---	26735	---		16	-	-	-	
	-	-	-	17		---	---	23413		18	-	-	-	
PANEL P1 & P1A VIA XFMR	150	3	19	19	90554	35767	---	---	16537	20	20	3	25	RTU-3
	-	-	-	21		---	36528	---		22	-	-	-	
	-	-	-	23		---	---	34795		24	-	-	-	
PREPARED SPACE	100	3	25	25	0	5000	---	---	5000	26	26	1	25	EDC-2
	-	-	-	27		---	5000	---	5000	28	28	1	25	ECH-1
	-	-	-	29		---	---	0	0	30	30	1	20	SPARE
PREPARED SPACE	100	3	31	31	0	0	---	---	0	32	32	3	100	PREPARED SPACE
	-	-	-	33		---	0	---		34	-	-	-	
	-	-	-	35		---	---	0		36	-	-	-	
TOTAL AMPS: 607.3						188066	166441	150169	TOTAL WATTS: 504676					

REMARKS:
FED FROM MCB.

01/13/2015

P1

VOLTAGE: 120/208 | PH & WIRES: 3P 4W | BUSES: 225
MAIN BREAKER: 225A MAIN BRKR | AIC RATING: SEE SPECS | MOUNTING: SURFACE
LOCATION: ELECTRICAL ROOM | FEEDER: SEE POWER RISER

LOAD DESCRIPTION	AMP	POLE	DWG CRKT NO.	POLE ID	WATTS	WATT LOADS PH A	PH B	PH C	WATTS	POLE ID	DWG CRKT NO.	POLE	AMP	LOAD DESCRIPTION
TUB 1 OF 1 - REMARKS:														
RCPTS - CORRIDOR	20	1	1	1	1600	2000	---	---	400	2	2	1	20	RCPTS - MENS TOILET
RCPTS - OFFICE	20	1	3	3	1000	---	1400	---	400	4	4	1	20	RCPTS - WOMENS TOILET
RCPTS - OFFICE	20	1	5	5	1000	---	---	2000	1000	6	6	1	20	RCPTS - CONFERENCE ROOM
RCPTS - OFFICE	20	1	7	7	1000	1400	---	---	400	8	8	1	20	RCPTS - CONFERENCE ROOM
RCPTS - OFFICE	20	1	9	9	1000	---	1600	---	600	10	10	1	20	RCPTS - BREAK ROOM
RCPTS - RECEPTION	20	1	11	11	600	---	---	1200	600	12	12	1	20	RCPTS - BREAK ROOM
RCPTS - WORK ROOM	20	1	13	13	200	900	---	---	700	14	14	1	20	* RCPTS - BREAK ROOM (REF)
RCPTS - OFFICE	20	1	15	15	1000	---	1200	---	200	16	16	1	20	RCPTS - BREAK RM (COUNTER)
RCPTS - OFFICE	20	1	17	17	1000	---	---	1200	200	18	18	1	20	RCPTS - BREAK RM (COUNTER)
RCPTS - OFFICE	20	1	19	19	1000	1200	---	---	200	20	20	1	20	RCPTS - BREAK RM (COUNTER)
RCPTS - OFFICE	20	1	21	21	1000	---	1000	---	0	22	22	1	20	SPARE
RCPTS - SERVER (BKBD)	20	1	23	23	200	---	---	200	0	24	24	1	20	SPARE
RCPTS - SERVER (BKBD)	20	1	25	25	200	200	---	---	0	26	26	1	20	SPARE
RCPTS - SERVER (COUNTER)	20	1	27	27	400	---	400	---	0	28	28	1	20	SPARE
RCPTS - SERVER (COUNTER)	20	1	29	29	400	---	---	400	0	30	30	1	20	SPARE
RCPTS - SERVER (RACK)	20	1	31	31	200	200	---	---	0	32	32	1	20	SPARE
RCPTS - SERVER (RACK)	20	1	33	33	200	---	2176	---	3952	34	34	2	30	AC-1 (SERVER ROOM)
RCPTS - SERVER (UPS)	30	1	35	35	2000	---	---	3976		36	-	-	-	
SPARE	20	1	37	37	0	600	---	---	600	38	38	1	20	RCPTS - ROOF MTD
SPARE	20	1	39	39	0	---	210	---	210	40	40	1	15	EF-8, 9 & 10
SPARE	20	1	41	41	0	---	---	528	528	42	42	1	15	EF-6
RCPTS - OPEN OFFICE	20	1	43	43	800	2000	---	---	1200	44	44	1	20	RCPTS - CORRIDOR
RCPTS - OPEN OFFICE	20	1	45	45	1200	---	2200	---	1000	46	46	1	20	RCPTS - KELLER ROOM
RCPTS - OPEN OFFICE	20	1	47	47	1200	---	---	2000	800	48	48	1	20	RCPTS - TRAINING
RCPTS - OPEN OFFICE	20	1	49	49	1200	1800	---	---	600	50	50	1	20	RCPTS - TRAINING
RCPTS - OPEN OFFICE	20	1	51	51	1200	---	2200	---	1000	52	52	1	20	*1 RCPTS - QUARTERS
RCPTS - OPEN OFFICE	20	1	53	53	1200	---	---	2200	1000	54	54	1	20	*1 RCPTS - QUARTERS
RCPTS - OPEN OFFICE COPIER	20	1	55	55	1500	1700	---	---	200	56	56	1	20	RCPTS - WOMENS BATH
SPARE	20	1	57	57	0	---	200	---	200	58	58	1	20	RCPTS - MENS BATH
SPARE	20	1	59	59	0	---	---	1400	1400	60	60	1	20	RCPTS - TRUCKERS LOUNGE
SPARE	20	1	61	61	0	1200	---	---	1200	62	62	1	20	RCPTS - TRUCK LOUNGE (VEND)
SPARE	20	1	63	63	0	---	1200	---	1200	64	64	1	20	RCPTS - TRUCK LOUNGE (VEND)
SPARE	20	1	65	65	0	---	---	1200	1200	66	66	1	20	RCPTS - TRUCK LOUNGE (VEND)
SPARE	20	1	67	67	0	0	---	---	0	68	68	1	20	SPARE
SPARE	20	1	69	69	0	---	0	---	0	70	70	1	20	SPARE
SPARE	20	1	71	71	0	---	---	0	0	72	72	1	20	SPARE
TOTAL AMPS: 251.5						30255	31016	29283	TOTAL WATTS: 90554					

REMARKS:
FED FROM PANEL MDP VIA TRANSFORMER., PROVIDE WITH FEED THROUGH LUGS TO SERVE PANEL P1A., * = GFCI CIRCUIT BREAKER., *1 = ARC-FAULT CIRCUIT BREAKER.

01/13/2015

HARRIMAN

AUBURN PORTLAND MANCHESTER

HARTT TRANSPORTATION

Auburn, ME

Harriman Project No.	14507

Key Plan | Proj North

REGIONAL ELECTRIC LLC
Design Installation Service
207 795-7800

Issues and Revisions

Mark	Date	Description
--	11-14-14	PROGRESS
--	12-08-14	PROGRESS
--	01-14-15	FOR CONSTRUCTION

STATE OF MAINE
JOHN W. TARR
No. 7700
LICENSED PROFESSIONAL ENGINEER

Drawing Scales

PA / PE: JWT
Drawn By: JMB

© 2015 Harriman Associates

SCHEDULES

E60.1